

ATM-RISK ASSESSMENT

TASK: Digging Post Holes by Hand RA No: ATMF)20/	008
EQUIPMENT / MATERIALS USED	Shovels, Picks						
PERSONS AT RISK:	FE	FENCING / LANDSCAPING OPERATIVES, PERSONS IN THE VICINITY, OTHER EN					
		CONTRACTORS, VISITORS, MEMBERS OF THE PUBLIC. (All operatives or teams of operatives are to ensure that the daily on-site risk assessment is completed prior to commencing any work of the complete of the commencing and the complete of the					
	site			· · · · · · · · · · · · · · · · · · ·			
HAZARD / RISK		RIS		CONTROL MEASURES	RESIDUAL		
		LEV				RISK	
	S	L	RL		S	L	RL
Manual handling	3	3	9	Where possible, the need for hand digging will be avoided by employing the use of a tractor and auger (mechanical means)	3	2	6
Back Strain, Upper Limb Strain,		All ATM operatives will be provided with manual handling training and information.					
musculoskeletal disorders				Where digging is to be carried out by hand, operatives are to take regular breaks and where possible, rotate tasks in order to reduce the risk of Repetitive strain injury (RSI) and musculoskeletal injuries.			
Cuts and abrasions	2	3	6	All operatives involved in this task are to wear ATM Ltd's standard PPE issue, including suitable gloves and suitable safety footwear.	1	2	2
Contact/Collision with moving vehicles	5	3	15	All operatives involved in this task shall wear ATM Ltd's standard PPE issue and high visibility clothing compliant with both ATM Ltd's policies and the clients.	5	1	5
Serious injury, fatality				All site traffic rules shall be adhered to whilst on site. Due to the nature of the site, singular track access, all machine operations will be supervised by a banksman and operations paused to give way to the public.			
				All company vehicles are to undergo a daily vehicle pre - use check ensuring that all safety features such as lights, reversing alarms etc are fully functional.			

ATMRA2020/008		Priginal Author:	Rob Whamond	Date:	01-06-2021		
		Reviewed By:	Dale Nelson	Next Review Date:	01-06-2022		
Use the table below to calculate the	ne severity and like	elihood. (Severity X Likelihood = RISK)	ı	Use the table below to indicate whether t	he Residual Risk Rating is:		
	ty / Loss of Limb. 4	4 Serious Injury. 3 Moderate. 2 Minor		1 – 6 = Low Risk	Page 1 of 3		
Injuries. 1 Negligible. Likelihood of Harm; 5 Almos	0 0			7 – 11 = Medium Risk			
I Inlikely		, ,		12+ = High Risk			



ATM-RISK ASSESSMENT

111 111 11 11 11 11 11 11 11 11 11 11 1		RISK LEVEL		CONTROL MEASURES		RESIDUAI RISK	
	S	L	RL		S	L	RL
Underground Services Fire, explosion, burns, electric shock, serious injury, fatality	5	3	15	Before any work is allowed to take place, the ATM site supervisor/foreman will ensure that he has discussed the area of work with the client / main contractor, and has assured himself that there are no underground services that may present a danger to his operatives. If underground services have not been identified by the client / contractor, prior to operations commencing. The contractor or client will be requested to CAT and Genny Scan the area before any work can commence. If services are identified onsite, the client / contractor will request service drawings from the utility owner and provide them to the operatives site. Where underground services do exist, they are to be clearly marked using paint/chalk and annotated on any site diagrams. Trials holes maybe required, to track the service. Safe digging techniques are to be used at all times when digging near to underground services. When digging next to underground services, only insulated hand tools are to be used. Mechanical tools and equipment are not to be used for digging within 1 metre of an identified underground service, this distance maybe increased to comply with permits to breakground. Emergency and Utility Company's telephone numbers should be gained from the client/main contractor prior to any work commencing. Should any underground service be struck. Work is to stop immediately, barriers be erected and they are cordoned off until such a time that the incident has been cleared and permission to restart work, has been gained from the Utility Company. Refer to ATMRA2020/050 Underground Services for control measures. All works involving underground services (HSG47)	5	1	5

ATMD A 2020 / 009	Original Author:	Rob Whamond	Date:	01-06-2021		
ATMRA2020/008	Reviewed By:	Dale Nelson	Next Review Date:	01-06-2022		
Use the table below to calculate the severity	and likelihood. (Severity X Likelihood = RISK)		Use the table below to indicate whether t	he Residual Risk Rating is:		
1	f Limb. 4 Serious Injury. 3 Moderate. 2 Minor		1 – 6 = Low Risk	Page 2 of 3		
Injuries. 1 Negligible. Likelihood of Harm; 5 Almost Certain,			7 – 11 = Medium Risk	_		
I Inlikely	· · · · , - · · · · , · · · · · · · · · · · · · · · · · · ·		12+ = High Risk			



ATM-RISK ASSESSMENT

HAZARD / RISK	RISK LEVEL			CONTROL MEASURES		RESIDUAL RISK		
S L RL		RL		S	L	RL		
Slips, Trips and Falls Cuts, abrasions	3 3 9		9	All staff are to take care when working on any uneven ground or adverse weather conditions. Any such hazards should be highlighted during the on-site risk assessment process and all operatives reminded of the possible hazards that may exist. Operatives shall be required to wear suitable safety footwear when completing work activities and ensure they keep their footwear free from muck build up, to maintain good grip. Ensure that all materials are cleared away from access and egress areas	3	2	6	

ATMRA2020/008		Original Author:	Rob Whamond	Date:	01-06-2021		
		Reviewed By:	Dale Nelson	Next Review Date:	01-06-2022		
Use the table below to calculate	the severity and	likelihood. (Severity X Likelihood = RISK)	Use the table below to indicate whether the Residual Risk Rating				
· · · · · · · · · · · · · · · · · · ·				1 – 6 = Low Risk	Page 3 of 3		
Injuries. 1 Negligible. Likelihood of Harm; 5 Almost Certain, 4 Very Likely, 3 Fair Chance, 2 Remote, 1 Ve		erv Likely . 3 Fair Chance . 2 Remote. 1 Verv		7 – 11 = Medium Risk			
Unlikely.	,			12+ = High Risk			